

PRE-TERM CABLE ASSEMBLIES CONFIGURATOR

Part Number

FA / -

1 = Fiber Type

S = Singlemode
M = Multimode

2 = # of Strands

004	048
006	060
012	072
018	096
024	144
036	288

3 = Cable Type

A = Indoor, Riser Rated
B = Indoor, Plenum Rated
C = Indoor/Outdoor, Riser Rated
D = Indoor/Outdoor, Plenum Rated
E = Outside Plant/Outdoor

4 = Side A

1 = ST	8 = MTRJ (M)
2 = SC	9 = MTRJ (F)
3 = FC	10 = Biconic
4 = LC	11 = D4
5 = SCAPC	12 = MTP (F)
6 = FCAPC	13 = MTP (M)
7 = Open	14 = LCAPC

5 = Side B

1 = ST	8 = MTRJ (M)
2 = SC	9 = MTRJ (F)
3 = FC	10 = Biconic
4 = LC	11 = D4
5 = SCAPC	12 = MTP (F)
6 = FCAPC	13 = MTP (M)
7 = Open	14 = LCAPC

6 = Breakout Length

1 = 12"
2 = 18"
3 = 24"
4 = 36"
5 = 48"
6 = 60"
7 = 72"

7 = Furcated Breakout

N = 900um Legs
Y = 2mm Furcation

8 = Pulling Eye

N = None
Y = Yes, One Side
Y2 = Yes, Both Sides

9 = Length

XXXF = Feet
XXXM = Meters

10 = Additional Specifications

10G = OM3 (50um)
10G4 = OM4 (50um)
BI - Bend Insensitive
AR = Armored OSP
AIA = Aluminum Interlocking Armor
MAR = Micro-Armor Style
LT = Loose Tube
MD = Micro Distribution Style
RIB = Ribbon Style
SJSA = Single Jacket Single Armor
DIE = Dielectric
YL = Yellow 2mm Furcated Legs

Custom Breakout
Lengths and
Styles Available

Need assistance with selecting the correct pre-term cable assembly? Contact one of our experienced sales engineers to review your specific project needs.

Toll Free **866-518-5858**
or email sales@amerifiber.com